

Digital Risk Twin-Enabled Operational Readiness (OR) Lifecycle Transforming Reliability for Mining, Oil & Gas, and Energy Projects


*A unified DRT framework delivering **risk-aware design**, readiness tracking, and predictive operations across asset-intensive industries.*

The Digital Risk Twin (DRT) transforms Operational Readiness (OR) by integrating design, risk, and operational data into a single digital model. This enables real-time, risk-based decision-making from concept through operations, ensuring that readiness, reliability, and performance targets are met across the full project lifecycle.


Lifecycle Coverage:

Concept → Feasibility → FEED → Detailed Design → Construction →
Commissioning → Operations

Each stage includes risk quantification, design validation, and readiness verification; providing early visibility and control over project reliability performance.




Stage 2: Feasibility



Stage 3: Front-End Engineering Design (FEED)



Stage 4: Detailed Design & Procurement



Stage 5: Construction

INPUT:

- Civil, mechanical, electrical works executed.
- Equipment installed.
- Responsible Persons: EPC contractors, inspectors.

DRT Value:
Provides risk-adjusted
schedule forecasts.
??

INPUT:

- OR staff check for safe access, tag alignment, maintainability. Punch-listing issues.
- Warehouse operational. Inventory and barcode systems tested.
- Responsible Persons: OR engineers, maintenance SMEs, Logistics managers, IT team.

DRT Value:
Resolves issues before
commissioning and mitigates
supply chain risks.

INPUT:

- OEMs deliver classroom, simulator, and field training. Competency assessments completed.
- Responsible Persons: OEM trainers, training coordinators, workforce.

DRT Value:
Ensures staff are job-ready
before start-up.

Construct facilities and install equipment

OR team mobilized on site for reviews

Confirm warehousing, logistics, and monitoring systems

Update DRT with as-built installation data and verified functionality

Begin operator/maintainer training with OEMs

Update DRT with human reliability analysis (HRA) parameters

Update DRT with schedule deviations (if any) and progress data

DRT Execution:

- Simulates schedule deviations (delays, rework, late deliveries) and their impact on OR milestones.
- Recalculates effects on downstream activities — commissioning, reliability testing, and OR gates.
- Quantifies production readiness risk and startup slippage.
- Enables proactive recovery actions (e.g., fast-tracking commissioning or adding resources).

DRT Execution:

- DRT simulates as-installed systems to verify functionality and performance.
- Identifies readiness gaps and validates system behavior before commissioning.
- Update in real time to reflect actual installation and ensure a smooth transition to start-up.

DRT Execution:

- Models human reliability and competency gaps by simulating operator performance, training levels, and human error probabilities to assess their impact on overall system availability and safety.

Construction OR Gate Output:

- Installed systems verified for operability and logistics readiness; risks resolved before commissioning handover.

Stage 6: Commissioning & Start-Up

INPUT:

- System commissioning (cold → hot → performance). Test plant against design capacity.
- Responsible Persons: Commissioning engineers, EPCM, operators.

DRT Value:
Confirms reliability targets are achievable.

Execute commissioning plan and integrated testing

5
Update DRT with actual data as applicable

INPUT:

- Operators observe, then progressively take over.
- Conduct fire, spill, and evacuation drills. Document response times.
- Simulate same events in DRT. Compare simulated vs. real outcomes.
- Responsible Persons: Operators, commissioning team, HSE team, emergency responders.

DRT Value:
Reinforces operator learning and validates emergency readiness.

Operators shadow commissioning teams

DRT Execution:
- Actual commissioning data fed into DRT for validation vs. design.

Emergency drills and HSE validation

DRT Execution:
- Capture actual downtime from historian and compare with design RAM targets.
- Analyze deviations to refine MTBF/MTTR values and update reliability model.

INPUT:

- 72-hour (or as specified) continuous run test. Track downtime.
- Responsible Persons: RAM engineers, operations.

DRT Output:
Analyze deviations to refine MTBF/MTTR values and update reliability model.

Reliability testing against design RAM targets

Commissioning & Start-Up OR Gate Output:
- Plant performance validated against design RAM targets with readiness proven for safe operational takeover.

6

Stage 7: Operations / Handover

